

The Status of ITER; The ITER Design Review

Town Hall Meeting on ITER – APS Conference Orlando 13th November 2007

ITER Design Review Coordinator G. Janeschitz

1

The Status of ITER; the ITER Design Review - G. Janeschitz - November 2007



Outline

>ITER Organization and Status


- Scope and Goals of the Design Review
- >How was the design review performed

Some examples of the most important issues and their solutions

2

>Outlook

Management Structure of the ITER Organization





ITER Agreement, Recruitment and Consultants

> ITER Agreements entered into force on 24 October, 2007.

Headquarters Agreement has been signed between the IO and the state of France on 7 November, 2007.

> ITER-Organisation Staffing:

- > As of October 31, the IO has a total of 194 staff
- > 153 professionals
- 41 support staff
- Around 65 persons on site under service contracts

Total of about 260 persons at the site in Cadarache

Temporary ITER Offices

ITER Dungeon



Extension Bureau: completed in March, occupied by 75



Building 507: made available by CEA Fusion, occupied by 38



Building 519: occupied by ~ 150 (designed for 140 – 150)


> Presently available maximum capacity 150 + 38 + 75 = 263




Roles and Responsibilities for Construction

6

All domestic agencies will be established latest end of 2007





Preliminary bottom up schedule suggests up to 3 years delay – work ongoing to bring it as much as possible in line with official schedule



The ITER Design Review Goals Methodology and Statistics

8

The Status of ITER; the ITER Design Review - G. Janeschitz - November 2007

The Design Review: 2001-2006 History

1998 to 2006 (EDA, CDA and ITA) History
 1999 to 2000 three options studied (LAM, IAM, HAM)
 2000 to 2001 only one year for detailed design of IAM
 2001 to 2005 ~ 35 larger design changes recorded but not approved because there was no body to this
 200 issues with the design were registered by the ITER

team during the above time and not solved until 2006

Negotiations were undertaken on the basis of the 2001 design/baseline/cost.

An intermediate baseline (2004) was submitted but never formally accepted, but this intermediate baseline was the basis of the design review which took place this year



Goals of the Design Review (1)

The first goal for 2007 was to create a new Baseline Design 2007 which

Confirms or redefines the physics basis and requirements for the project

➢is the basis for the procurement of the long lead items (Vacuum Vessel, Magnets, Buildings),

Provides input for the Preliminary Safety Report

For components and systems which are procured at a later date or for issues with lower priority work will continue into the year 2008



- The second goal was to base the ITER design decisions also in detail on a broad basis by involving the worldwide fusion community (physics and engineering)
 - Thus the Fusion community and the parties can take ownership of the project

The third goal was to broaden the knowledge basis into the parties which is essential for a successful procurement of the ITER components in kind

A significant part of the technical coaching of industry and of the QA will rest with the Domestic Agencies (DAs)



Design Review was performed by 8 Working Groups ~150 members

WG-1 Design Reqs. & Physics Objectives. Chair: P.Thomas; IO D.Campbell

WG-2 Safety and Licensing Chair: J-P Perves; IO J-P.Girard

WG-3 Site and Buildings Chair: C.Strawbridge; IO J.Sovka

WG-4 Magnets Chair: M.Huguet; IO N.Mitchell

WG-5 Vacuum Vessel Chair: Songtao Wu; IO K.loki

WG-6 Heating and Current Drive Chair: J.Jacquinot; IO A.Tanga

WG-7 Tritium Plant Chair: D.Murdoch; IO M.Glugla

WG-8 In-Vessel Components Chair: Igor Mazul; IO M.Pick/C.Lowry The membership consists of the leading experts of the fusion community in each party

The groups have written manifestos explaining the scope of their work (see ITER technical web)

In order to solve issues work packages have been agreed with the parties based on the work plans established by the design review working groups


12

=> adding ~ 160 more persons



ITER Issues

(Link: ITER Issues Data Base)



~ 200 issues existed for several years but were for different reasons not solved or rejected

Another ~ 250 were added by the parties last autumn when the design review process started


Thus ~ 450 issue cards existed when the design review working groups were formed in December of 2006 and started their work

186 issues require consideration by more than one

Group The State of ITER; the ITER Design Review - G. Janeschitz - November 2007



Issues have been prioritized Distribution of Issue Priorities



The dark blue issues are the high priority ones

They and the medium priority issues had to be solved until autumn 2007 as a minimum

in order to allow the procurement of the long lead items to go ahead as scheduled


and in order to be able to launch the preliminary safety report in time

We achieved more than that !!

The Status of ITER; the ITER Design Review - G. Janeschitz - November 2007



Further Condensation of (High) Priority Issues



The high priority issues, the medium and some low priority issues have been condensed into fewer issue families covering the same range of problems

Thus ~ 80 issue families remained to be tackled

e.g. in Physics ~ 80 issues were condensed into 14



Resources and Interfaces between WGs

Resources:

The working groups have established work plans with the aim to solve all 80 high priority issue families by September 2007 and to document together with the IO the resulting design in the Baseline 2007 (November)

The extra PT resources required for 2007 were 82.4 PMY distributed over the 7 parties

Interface meetings:

Approximately every 4 to 5 weeks interface meetings between the DRC, the chairmen, the ITER co-chairmen of the WGs and a few specialists took place either in person or by phone / video conference

These meetings have proven to be extremely useful and productive and were essential for a successful progress of the design review process

The Status of ITER; the ITER Design Review - G. Janeschitz - November 2007



Timeline for Implementation of the Baseline

Two meetings at technical level with Members to discuss DR recommendations followed by TCM (25 and 26)

≻ July 16-19	DONE
➢ Sept 17-20	DONE

STAC, TAG, MAC+STAC to discuss officially with the Members
 STAC: Sept 5-6 DONE
 TAG: Oct 3-5 DONE
 MAC+STAC: Nov 5-8 DONE
 a few DCRs rejected by IO to be reexamined
 CPWG: Nov 8-9 DONE

Council meeting: Nov 27-28




- DCRs have been mostly adopted for study ("ongoing") at the decision making meetings and thus enter the normal ITER design change process.
- As soon as a design is mature enough (feasibility demonstrated, requirements fulfilled, it is a significant improvement on the existing design) it will be adopted into the baseline while detailed work will continue
- All high priority items will thus be part of the new baseline 2007

> All DCRs "ongoing" are cited in the 2007 baseline

> After STAC a few rejected DCRs re-opened for study

Issues Data Base after the Design Review




More than 400 Issues have now been closed, dropped or are covered in a DCR About 67 Issues will still be "ongoing" at the end of 2007, and will be handled during the next years **All important issues are on the way to be solved (including the ones which were contained in a rejected DCR and now have been re-opened by STAC)**



Status of DCRs

- > The ITER DCR system tracks all baseline design changes from the FDR-2001
- > Currently (after TCM-26) it holds **139** DCRs.
 - (4 in "Draft", 61 "Ongoing" (for study), 28 accepted, 27 Completed, 19 Dropped)



DCR Status after TCM26 21th Sept 2007



The ITER Design Review Results

>The most important Issues and their Solutions

The corresponding DCRs were accepted by IO for study or re-introduced by STAC last week


21

All high risk items for ITER are now under study and proper solutions will most likely be implemented

The Status of ITER; the ITER Design Review - G. Janeschitz - November 2007

Sensitivity of performance on ITER machine parameters: B_T , elongation, etc

 P_{α} [MW]




- Operation diagram for ITER calculated with integrated model ICPS
- Core model is MMM more optimistic than GLF23
- Blue dashed line represents impact of low rotation, purple line full parameters, red 95% B_T or elongation 1.6 instead of 1.7 at 100% B_T, green 90% B_T
- To achieve the goals of ITER routine operation at the design parameters (5.3 T; 15 MA) is essential – not standard on todays machines!



Main Problems in Plasma Control area

- PF system is marginal, in particular for low l_i
 saturation of some coils in parts of the discharge
 e.g. early X-point formation difficult, etc
- Vertical Stability is marginal above I_i = 1
- CS flux swing is marginal / too low if l_i > 1
- ELM control is essential RMP coil set needed
- Proposals to improve the situation are on the table and were either already accepted for study by the IO or reintroduced by STAC





In the case of PF6 made of NbTi, in 15 MA scenario:

- ➢ operation with I_i < 0.8 hits the limit on magnetic field on PF6 (5.9 T) and operation with I_i < 0.75 hits the limit on current in PF2 (44 kA).</p>
- operation with I_i < 0.75 0.8 requires more difficult plasma shape feedback control (control of 7 plasma-wall gaps, instead of 6 gaps, without using of PF6 and PF2).

In the case of PF6 made of Nb₃Sn, in 15 MA scenario:

- ➢ operation with I_i < 0.75 hits the limit on current in PF6 (49 kA) and operation with I_i < 0.65 hits the limit on current in PF2 (44 kA).</p>
- operation with I_i < 0.65 0.75 requires more difficult plasma shape feedback control (control of 7 plasma-wall gaps, instead of 6 gaps, without using of PF6 and PF2).

The Status of ITER; the ITER Design Review - G. Janeschitz - November 2007

H.Fujieda



Shape Control - required improvements

Change conductor in PF6 to Nb₃Sn, => up to 20% increase of current possible

- Increase capability of PF2 and PF5 by 10% by adding winding packs
- ➤ The total cost of these changes would amount to ~ 8.4 M€ estimate of EU team supported by ITER magnet division
- ➢ IO did not agree to these changes, wants to sub cool to 3.8 K
- > However, sub-cooling was foreseen as mitigation of a coil failure
- STAC asks for change => study by risk assessment group

Vertical Stability


High elongation ~ 1.85 (1.7 in "Big ITER")

Thick double-walled vacuum vessel

Saturation of P2 and P5 in certain conditions

The range of *li*(3) between 0.7 and 1.0 has been specified for the design of the ITER PF system

There is a problem with vertical stability in most discharge phases but they are gravest in Ip ramp-up and ramp-down (high I_i)



Solution: Improve Passive Stabilization

Connection of toroidal rings of blanket modules provides improved passive stability characteristics:


	Stability margin (CREATE)	Stability margin (EFDA)	Growth rate (ms)	M_{ϕ}	BAP (mm)
No blanket rings	0.27	0.37	68	3°	20.8
Blanket rings 1 & 5	0.31	0.43	94	9°	31.1
Blanket rings 2 & 4	0.33	0.44	98	11°	33.0
Blanket rings 7 & 11	0.28	0.38	75	7°	25.2
Blanket rings 8 & 10	0.29	0.39	79	9°	26.9
All blanket rings	0.39	0.52	150	22°	52.5

⇒ Studies of possible mechanisms for toroidal coupling of blanket modules

- ⇒ Analysis of disruption forces
- ⇒ Analysis of equilibrium/ control implications

⇒Option of increasing voltage in PF coils from 6 to 9kV rejected by IO

The Status of ITER; the ITER Design Review - G. Janeschitz - November 2007





Flux Available for Burn in ITER


At high l_i during current ramp potentially no flux left for flat top

Difficult approach to ITER reference scenario

Possibly mitigation by increasing flux by ferromagnetic insert in the solenoid and by increasing resistivity in VV

Not yet studied by IO







Plasma Control related DCRs

DCR requiring li-q space experienced in experiments was accepted

DCRs to add 2nd VS circuit using CS and to increase the VS1 voltage to 9kV were dropped – STAC wants study !

DCR for extra double-pancake to P2/P5 awaits the "Coil Risk Group" – STAC asks for studying upgrade !

DCR for Increasing the PF6 capability (NbSn) awaits the "Coil Risk Group" – STAC asks for studying upgrade !

≻No DCR for CS flux swing issue – not studied in IO

EU party asks for increased flux swing or provide current drive- improve PF6, PF2 & PF5 and keep subcooling as a back-up, in case of failure

Expected ELMs and the Mitigation Problem

Permissible ITER ELMs ~1%
 of the pedestal energy.

Expected not mitigated ELMs for ITER low collisionality plasma are ~20% of the pedestal energy.

> ELM Energy Reduction necessary by ~10 to 20 times






Figure 17. ELM energy normalized to the pedestal energy versus pedestal collisionality. The multi-machine data collected by the ITPA Divertor Group include density scans as well as varying configurations [166].





ELM suppression by ergodization


- Ergodization works for D3D (and JET).
- WG-1 has proposed to use a set of 36 Resonant Magnetic Perturbation coils similar to DIII-D












Picture frame coils

Blanket-Vessel Interface coils

Three concepts studied by WG1and costed by IO

Only 36 coil option will most likely work change location to between VV shells


The Status of ITER; the ITER Design Review - G. Janeschitz - November 2007




Port-plug coils

Vacuum Vessel – ELM coils between shells

STAC ask for this study until their next meeting





A working group (IO, EU, US, KO) will study this option

Conceptual design to be available until end of February

Then check schedule – costand safety impact

The Status of ITER; the ITER Design Review - G. Janeschitz - November 2007




Main Problems in Blanket area

- Update of FW loading conditions require improvements of the FW geometry
 - > Hiding leading edges
 - > prepare for toroidal peaking factors increased power loads
 - Possible plasma start up on FW remove port limiters
- Provide electrical connectors in toroidal direction to improve vertical stability
 - > In situ separable FW needed
- Improve RH water connector and review and improve RH approach
- Cooling water manifold is not RH compatible
 - Improve design or integrate the manifold into the blanket modules

STAC emphasized strongly the RH issue

General Concept Differing Geometry around Wall







Detailed shaping of the First Wall to shadow all exposed edges Near 2nd X-point

Inner Wall


36 of 440 modules








CAD view of 3 adjacent strapped shield modules



Manifold design

The Status of ITER; the ITER Design Review - G. Janeschitz - November 2007





Summary of Major Changes

- > **Physics**: ELM coils cost driver, vertical stability, shape control
- Safety: No Carbon in the Tritium Phase + Tritium Management
- Buildings: Hot cell remains a challenge potential cost driver; re-optimization of layout and inclusion of Magnetic fields in the building layout.
- Magnets: No major changes. PF's may change because of Plasma control. <u>Cold</u> testing is the biggest change and a cost and schedule driver.
- Vacuum Vessel: no major changes blanket manifold integrated with blanket ???
- H&C drive: Development of NB asap and decouple RF installation from Assembly hall, consider upgrade of ECRH by 20 MW to allow for possible delay in beams
- **Tritium plant**: Complete redesign and layout but no major cost changes
- In Vessel Components: Several adaptations and changes:
 - Blanket attachment and water cooling manifold, electrical connections
 - Use of Tungsten in Tritium phase for divertor
 - Tiling adjustment of first wall in several areas to deal with misalignments and heat loads
 - > Use of 18 inward moved columns (~1cm) and eventual no movable limiters
 - > LOTS OF DETAILED DESIGN TO BE DONE

Diagnostics and CODAC are dealt with separately

The Status of ITER; the ITER Design Review - G. Janeschitz - November 2007



Cost and schedule impact of the design review (very preliminary)

- Approximately 80 DCRs are related to the design review process
- ➤ The total cost of the design review related changes will be in the order of 150 M€ +- 50 M€ including the items asked for by STAC
- Most changes have a small cost impact or non, only a few have a large cost impact
 > (e.g. ELM coils (40 to 55 M€) and magnet cold test (30 to 50 M€)
- Only a few changes will have a schedule impact
 magnet cold test (~ 3 month on TF procurement)
 ELM coils between VV shells (~ 6 month on VV)



Outlook

- The ITER Project moves rapidly towards reality
 - The team is being built up and starts to be able to fulfil its role (a lot remains to be done)
 - > A realistic schedule and cost will emerge towards the middle of 2008
 - > A new baseline design for the long lead items is available end of 2007
 - A decision on scope versus cost and schedule will have to be taken in 2008 by the ITER Council
- The design review has been very successful and was well supported by the world wide fusion community
 Decisions on the proposals have been taken in July and September
 A few complex problems continue to be under investigations
- We, the fusion community should continue to support the ITER project as much as possible
 - Only ITERs success will ensure our all success and that fusion will eventually become a major energy system